

WYKAZ ZJAZDÓW
przebudowa drogi gminnej
przez wieś ZABOROWO
od km 0+000 do km 2+060

Strona lewa					Strona prawa				
Lp.	Pikietaż	bez rur	z rurami	Uwagi	Lp.	Pikietaż	bez rur	z rurami	Uwagi
1	0+266	-	5		1	0+279,30	-	6	droga gminna
2	0+279,30	-	5		2	0+355	-	5	
3	0+350	-	5		3	0+397,50	5	-	
4	0+440	-	5		4	0+417	5	-	
5	0+490	-	5		5	0+430	5	-	
6	0+528,50	-	5		6	0+505,50	5	-	
7	0+600	-	5		7	0+557	5	-	
8	0+727	-	5		8	0+664	-	5	
9	0+866	-	5		9	0+708	-	5	
10	1+214	5	-		10	0+866	5	-	
11	1+233,70	5	-		11	1+233,70	5	-	
12	1+317,70	5	-		12	1+317,70	5	-	
13	1+343	5	-		13	1+359,50	5	-	
14	1+359,50	5	-		14	1+384	5	-	
15	1+384	5	-		15	1+421	5	-	
16	1+421,50	5	-		16	1+466	5	-	
17	1+466	5	-		17	1+523	5	-	
18	1+523	5	-		18	1+556	5	-	
19	1+556	5	-		19	1+573	5	-	
20	1+573	5	-		20	1+607	5	-	
21	1+607	5	-		21	1+630	5	-	
22	1+630	5	-		22	1+680	5	-	
23	1+680	5	-		23	1+713	5	-	
24	1+713	5	-		24	1+720	5	-	
25	1+720	5	-		25	1+813	5	-	
26	1+813	5	-		26	1+813	5	-	
27	1+843	5	-		27	1+843	5	-	
28	1+875	5	-		28	1+875	5	-	
29	1+960,50	5	-		29	1+960,50	5	-	
30	1+982	5	-		30	1+982	5	-	

Zestawienie:

Zjazdów razem $30 + 30 = 60$

W tym zjazdów z rurami o $30 - 13$ szt + 3 rezerwa = 16 szt $16 \times 5 + 1 = 81$ m
bez rur - 47 szt , 235 m

Ścianek czołowych betonowych prefabrykowanych $16 \times 2 = 32$ szt

Ścianek czołowych z darniny $47 \times 2 = 94$ szt

Nawierzchnia na zjazdach z pospółki grub. 10cm

$19 \times 25 \times 4,0 = 190$ $41 \times 1,50 \times 4,0 = 246$ $190 + 246 = 436$